

**Main 4 Core Cable and Change overs for Energization of Telecom & Chemical Engineering
Departments with 200 KVA Generator and WAPDA Supply (DUAL) at QUEST Nawabshah**

Schedule - B

Sr.	Description of Item	Quantity	Rate	Unit	Amount
1	Providing & Laying (Main or Sub main) PVC insulated & PVC Sheeted with 4 Core armoured copper conductor 600/1000 V size 240mm (S.I.No. 122 Page-14)	50 Mtr	18,513	P/Mtr	925,650.00
2	Providing & Laying (Main or Sub Main) PVC insulated with size 2-7/044 (6mm) copper conductor in 1" dia PVC conduit recessed in the wall or column as required. (S.I.No. 12 Page-02)	250 Mtr	341	P/Mtr	85,250.00
3	Providing & fixing Change over switch 500 V 500 Amp on prepared board. (S.I.No. 201 Page-30)	2 Nos	40,126	Each	80,252.00
4	Providing & Fixing Magnetic Contector FC300N as required & as per instruction of Engineer Incharge. (S.I.No. 260 Page-37)	2 Nos	106,010	Each	212,020.00
5	Providing & fixing & testing of earth points with 2'x2'x1/8" thick copper plate burried 5 Meter deep or to the depth of permanent water level which ever is less covered with charcoal and lime in specified ratio confirming to specification. Complete Job. (Non Schedule Item)	1 Job		Each	

Total Cost of Schedule Items Rs. 1,303,172.00

Add _____ % Above / Below Premium on Schedule Items Rs. _____

Cost of Non Schedule Item Rs. _____

Grand Total Rs. _____

Contractor Sign / Seal