

**Providing & Laying 3" dia Water Supply Line for Newly Constructed Buildings of  
Telecom & Chemical Engineering Departments at QUEST Nawabshah**

**Schedule - B**

<b>Sr.</b>	<b>Description of Item</b>	<b>Qty</b>	<b>Rate</b>	<b>Unit</b>	<b>Amount</b>
1	Providing, Laying UPVC pipe of Class C fixing in trench i/c cutting, fitting and jointing with solved cement i/c testing with water to a head of 90 meter or 300 Rft. <b>3" dia (S.I.No. 5 Page-24)</b>	3000 Rft	136.00	P/Rft	408,000.00
2	Excavation for Valve chambers <b>(N.S.I)</b>	130 Cft		P/Cft	
3	Providing & Fixing of gate valve 3" dia (Brass) <b>(N.S.I)</b>	4 Nos		each	
4	Providing & Fixing of Handle valve 1-1/4" dia (Brass) <b>(N.S.I)</b>	8 Nos		each	
5	Making connection with clamp, nuts, bolts and rubber packing etc complete 3x3 <b>(N.S.I)</b>	2 Nos		each	
6	Making connection with clamp, nuts, bolts and rubber packing etc complete 3"x1-1/4" <b>(N.S.I)</b>	8 Nos		each	
7	Preparation of valve chamber of size 1.5'x1.5'x3.0' with brick masonry and C.I cover etc complete. <b>(N.S.I)</b>	4 Nos		each	

Total (Non Schedule Items) Rs.

Total Schedule Item Rs. 408,000.00

Add \_\_\_\_\_% on Schedule Items Rs. \_\_\_\_\_

**Grand Total Rs.** \_\_\_\_\_

Contractor Sign & Seal