

Providing, Installation & Commissioning of 11 KVA HT Metering / Industrial Panel (VCB) P44:96 for new Independent Feeder at QUEST Nawabshah

Bill of Quantities (B. O. Q)

Part-A: HT Industrial Metering Panel

Sr.	Description of Item	Quantity	Rate	Unit	Amount
1	Providing, Installation including transportation & unload of 11 KVA HT Metering / Industrial Panel (VCB) including CTs, PTs and Safety instruments complete in all respect P44:96	1 Nos		each	
2	Testing, Commissioning & energization of HT industrial Meter panel	1 Jobs		P/Job	
3	Providing, making and testing of earth points with 2'x2'x1/8" thick copper plate buried 5 meter deep or to the depth of permanent water level which ever is less covered with charcoal and lime in specified ratio confirming to specification and as directed by engineer incharge.	2 Jobs		P/Job	
4	Providing, drawing, connecting & testing of 2-70mm ² bar copper conductor as earthing leads in 32mm dia G.I.pipe burried in ground or connected in R.C.C. or masonry as requiried from Panel Board to the earth plate, including, providing & fixing of plug for watering, complete with all accessories and fasteners and as directed by the engineer incharge.	2 Jobs		P/Job	
5	Providing, laying & connecting 2-70mm ² single core copper conductor as earth leads.	20 Mtrs		P/Mtr	
6	Providing & Installation of HT water proof / fire proof Kits outdoor type for HT cable 120 mm Single core complete	6 Nos		each	
7	Providing & Installation of HT water proof / fire proof Kits indoor type for HT cable 120 mm Single core complete	6 Nos		each	

Total Cost Rs. _____

Rupees: _____

Contractor Sign & Seal

Director Works
QUEST, Nawabshah

Director Finance
QUEST, Nawabshah

Project Director
SBBVUAS, Sakrand